



Excellence for Generations.

AN EMPLOYEE OWNED COMPANY



Princeton - Airport Runway Reconstruction

Princeton, Maine

Owner

Town of Princeton
15 Depot Street
Princeton, ME 04668
Jason Theriault - Vice Chair, Town Council
207-796-2744

Project Type

Runway & Taxiway Reconstruction

Sargent Corporation's Role

General Contractor

Engineer

Stantec
25 Sweden Street
Suite B2
Caribou, ME 04736-2503
Seth Lovley - Project Manager

Start / Finish

August 2017 - November 2017

Project Value

\$4.6 Million

Description / Significance

This project required the reconstruction of 4,300 linear feet of runway including a 20 foot fill on the south end to bring the runway up to compliance. Crews also reconstructed portions of Taxiways A & B and constructed a new Taxiway C. This contract required the airport to shut down for 100 days while crews completed the project. Rock excavation was completed using a D10 dozer and excavators with hoe rams.

Work included:

- 92,000 cubic yards of Common Borrow
- 20,000 cubic yards of Rock Excavation
- 77,000 cubic yards of Reclaiming
- 48,000 cubic yards of Subbase Gravel (P154)
- 8,900 cubic yards of Base Gravel (P208)
- 8,900 linear feet of Underdrain
- 6,500 linear feet of Storm Drain with 12 Basins
- 11,000 linear feet of electrical trenching
- 7,400 tons of Asphalt (M401)